SAYE ON TIME, LABOR, AND RISK WITH IWS®. CAST-IN-PLACE WINDOW SYSTEM

Tilt-up construction has long been valued for its speed, cost-efficiency, and strength. However, traditional punch or framed windows installed after panels are tilted often introduce added costs, labor inefficiencies, water leaks, ongoing caulking maintenance, alignment issues, and inconsistent aesthetics.

Integrated Window Systems® (IWS) has changed that with the only cast-in-place window system designed specifically for tilt-up construction. Engineered for performance and built to simplify the jobsite, the IWS system continues to draw interest from architects, general contractors, design-build teams, and concrete professionals seeking smarter, faster, and more reliable solutions.

CAST-IN-PLACE SYSTEM WITH IWS®

Our approach integrates clerestory punch windows directly into the tilt panel during casting. Frames are set into the forms before the concrete is poured, allowing them to be embedded, aligned, and securely positioned with precision from the start.





PLACE



TILT



Using a simple three-step process—Set \rightarrow Place \rightarrow Tilt—IWS eliminates many of the costly and time-consuming steps of traditional installations. Because the windows are cast in place, there's no need for exterior caulking or finishing work at the frame-to-concrete interface. This eliminates common failure points and dramatically reduces long-term maintenance.

REDUCE ERRORS & FINISH FASTER

IIWS takes away one of the most error-prone and labor-intensive steps in tilt-up construction and replaces it with our cast-in-place system. The result is a faster, cleaner, and more predictable process that delivers measurable savings. The advantages are clear:


- Labor Savings Reduce hours spent setting and placing windows after tilt.
- **Faster Schedules** Accelerate construction by eliminating framework, blocking, and patching.
- Fewer Mistakes Pre-installed units ensure alignment and consistency from the start.
- **Higher Profitability** Deliver tilt-up projects with windows already embedded, creating efficiency and added value.

The impact: Tilt contractors can now deliver tilt-up buildings with windows fully integrated into the panels—improving speed, safety, and quality while increasing profit margins for every stakeholder.

HIGH PERFORMANCE TECHNOLOGY

Each unit is rigorously tested to meet high performance standards for design pressure, wind load, and durability, and offers flexibility with full glass options, multiple colors, and compatibility with standard wall widths.

In the field, IWS's system has proven to streamline projects and improve outcomes for the entire build team, delivering faster coordination, lower risk, and more consistent results.



uPVC thermal conductivity is 1,000 times better than aluminum.

TITLE	RESULTS
AAMA/WDMA/CSA 101/I.S.2/A440-22	CW-PG100-FW 1524 x 1524 (60 x 60)
Design Pressure	±6240 Pa (±130.33 psf)
Air Infiltration	<0.10 L/s/m² (<0.01 cfm/ft²)
Water Penetration Resistance Test Pressure	960 Pa (20.05 psf)
Uniform Load Structural Test Pressure	±9360 Pa (±195.49 psf)
Forced Entry	Type D Grade 10

ADVANCING YOUR TILT-UP PROJECTS

As the tilt-up industry continues to evolve toward faster, safer, more durable, and more aesthetically refined buildings, cast-in-place window systems represent a true leap forward. For every stakeholder—contractors, architects, owners, and glaziers—the benefits are clear: lower cost, shorter schedules, higher quality, less maintenance, and better peace of mind.

If you're ready to explore how IWS's Cast-In-Place Window System can elevate your next project by reducing waste, streamlining coordination, and ensuring long-term performance, contact our team today for specifications, pricing, and a project consultation.

